

West Field Irrigation Company

Typical Drawings

Sheet Index

- 1 COVER SHEET
- 2 WFIC NOTES
- 3 TRASHRACK AND INLET STRUCTURE
- 4 OPEN DITCH TO PIPE TRANSITION AND STRUCTURE
- 5 WEIR AND WATERMAN C-10 CANAL GATE DETAILS
- 6 3-FOOT CIPOLLETTI WEIR
- 7 1-FOOT PARSHALL FLUME
- 8 90° V-NOTCH WEIR
- 9 IRRIGATION, BUBBLE UP BOX, AND LID DETAILS
- 10 IRRIGATION TURNOUT, AND DIVERSION BOXES
- 11 DIRECTIONAL DRILLING AND MICROTRENCHING
- 12 TRENCH DETAIL
- 13 CANAL BORING DETAILS
- 14 CONCRETE LINER

DISCLAIMER:

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

WEST FIELD
IRRIGATION COMPANY

DESIGNER:		CHAD BROWN		PROJECT LEADER:		CHAD BROWN					
DRAFTSMAN:		MATT GURR		FRONT DATE		March 31, 2025					
NO.	DATE	INTS.	REVISIONS								
			DESCRIPTION								

WEST FIELD IRRIGATION COMPANY		TYPICAL DRAWINGS	
COVER SHEET, SHEET INDEX		01- Cover Sheet.dwg	
JOB NO.		03/2017 WFIC West Field Irrigation Review\Standard Drawings	
CU 0000108		LAYOUT: Cover	

WEST FIELD IRRIGATION COMPANY (WFIC) NOTES

NOTES TO BE ADDED TO THE DRAWING SET UNDER HEADING LABELED "WEST FIELD IRRIGATION
COMPANY (WFIC) NOTES"

- ☐ APPLICANT MUST NOTIFY FRANSON CIVIL ENGINEERS AT LEAST 24 HOURS BEFORE CONSTRUCTION ON WFIC FACILITIES. CALL KYLE DeVANEY WITH FRANSON CIVIL ENGINEERS AT 801-756-0309. FAILURE TO DO SO MAY RESULT IN A \$5,000 FINE.
- ☐ WFIC CONTACT DURING CONSTRUCTION: BILL BECK, WFIC PRESIDENT, 801-836-6541
- ☐ ALL CONSTRUCTION AFFECTING IRRIGATION FACILITIES AND WITHIN THE WFIC RIGHT-OF-WAY MUST BE DONE TO WFIC STANDARDS.
- ☐ ALL BACKFILL MATERIALS SHALL BE COMPACTED TO A MINIMUM OF 95% STANDARD PROCTOR DENSITY.
- ☐ WORK CANNOT INTERFERE WITH DELIVERY OF IRRIGATION WATER. CONSTRUCTION ACTIVITIES THAT AFFECT WFIC FACILITIES MUST TAKE PLACE BETWEEN OCTOBER 31ST AND APRIL 1ST.
- ☐ IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT THE WORK SITE. ANY DAMAGE TO THE CANAL CORRIDOR CAUSED BY CONSTRUCTION ACTIVITIES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND APPLICANT.
- ☐ APPLICANT IS REQUIRED TO PERFORM COMPACTION TESTING AT THE APPLICANT'S COST. IF REQUESTED, COMPACTION TEST RESULTS SHALL BE SUBMITTED TO FRANSON CIVIL ENGINEERS. ALL FAILED MATERIAL SHALL BE REMOVED AND COMPACTED TO SPECIFICATIONS. TESTING MUST BE PERFORMED BY A LICENSED SOILS LAB.
- ☐ ALL CONCRETE USED IN CONSTRUCTION SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI. THE CONCRETE MIX SHALL INCLUDE BETWEEN 5% AND 7% AIR ENTRAINMENT.
- ☐ APPLY WATERSTOP RX, SWELLSTOP, OR WFIC ENGINEER-APPROVED EQUIVALENT TO ALL CONCRETE COLD JOINTS.
- ☐ PVC WATER STOP, OR EQUIVALENT, IS REQUIRED IN ALL JOINTS OF CAST-IN-PLACE CONCRETE TO PREVENT SEEPAGE BETWEEN THE SURFACES.
- ☐ FENCES DISTURBED DURING CONSTRUCTION ACTIVITIES MUST BE REPLACED AND RETURNED TO PRE-CONSTRUCTION CONDITIONS, OR BETTER.
- ☐ NEITHER WFIC NOR FRANSON CIVIL CAN VERIFY THE LOCATIONS OF UNDERGROUND FACILITIES. BLUE STAKES SHOULD ALWAYS BE CALLED BEFORE DIGGING (1-800-662-4111).

PIPES

- ☐ CONTRACTOR MUST DOCUMENT ALL NEW PIPES BY VIDEO CAMERA AFTER INSTALLATION AND BACKFILL. ANY PROBLEMS WITH JOINTS, LEVELS, SLOPES, ETC. DISCOVERED BY THE VIDEO TECHNICIANS MUST BE REPAIRED. A DIGITAL COPY OF THE VIDEO MUST BE SUBMITTED TO FRANSON CIVIL ENGINEERS.
- ☐ PRIOR TO BACKFILLING OF PIPES, THE CONTRACTOR MUST NOTIFY KYLE DEVANEY OF FRANSON CIVIL ENGINEERS SO A GPS SURVEY OF THE LOCATION AND ELEVATION OF THE INSTALLED PIPELINES CAN BE PERFORMED.
- ☐ PIPES CROSSING PERPENDICULARLY OVER OR UNDER THE IRRIGATION PIPE(S) SHALL HAVE A MINIMUM ONE-FOOT VERTICAL CLEARANCE.
- ☐ PIPES OR OTHER UTILITIES RUNNING PARALLEL TO THE IRRIGATION PIPE IN A SHARED EASEMENT SHALL BE PLACED A MINIMUM OF 5 FEET HORIZONTALLY DISTANCED FROM THE IRRIGATION PIPE.
- ☐ PIPES ENTERING OR EXITING A CLEANOUT BOX OR MANHOLE SHOULD BE SEALED AND GROUTED.
- ☐ PIPES ENTERING A CLEANOUT BOX OR MANHOLE MUST BE SECURED IN PLACE WITH A CONCRETE COLLAR.

IRRIGATION CLEANOUT BOXES AND MANHOLES

- ☐ KNOCK OUT BOXES AND MANHOLES ARE NOT ALLOWED. ALL BOXES AND MANHOLES SHALL BE PRE-CAST WITH CORED OPENINGS FOR THE PIPES OR SHALL BE CAST-IN-PLACE.
- ☐ PIPES ENTERING BOXES AND MANHOLES SHOULD BE CONCRETED ON THE OUTSIDE AND GROUTED ON THE INSIDE.
- ☐ IRRIGATION BOXES AND MANHOLES SHALL NOT BE BURIED. THEY SHALL EXTEND TO THE SURFACE OF THE FINAL GRADE. ANY EXISTING BOXES AND MANHOLES THAT WILL NOT EXTEND TO THE FINAL GRADE SURFACE SHALL BE EXTENDED TO MATCH THE FINAL GRADE. IF THE BOX HAS GATES, THE BOX SHALL EXTEND 6 INCHES ABOVE THE GROUND SURFACE.

INLET AND OUTLET STRUCTURES

- ☐ CANAL FLOOR AND EMBANKMENT MATERIAL REMOVED FOR EXCAVATION SHALL BE REPLACED WITH 12_INCH MINIMUM THICKNESS OF 10^{-6} CM/SEC PERMEABILITY CLAY MATERIAL, COMPACTED TO 95% STANDARD PROCTOR DENSITY IN 6-INCH MAXIMUM LIFTS.
- ☐ CANAL EMBANKMENT SHALL BE SHAPED TO MATCH THE EXISTING CANAL PRISM.

DIRECTIONAL DRILLING AND MICROTRENCHING

- ☐ WORK CANNOT INTERFERE WITH DELIVERY OF WATER. INSTALLATION ACTIVITIES MAY TAKE PLACE AT ANY TIME PROVIDED ULDC'S ACCESS TO OPERATION, MAINTENANCE, AND REPLACEMENT OF IRRIGATION FACILITIES IS NOT IMPACTED.
- ☐ BORE PITS MUST BE PLACED COMPLETELY OUTSIDE THE CANAL RIGHT-OF-WAY.
- ☐ FILL BORE PITS WITH A MIXTURE OF NATIVE MATERIAL AND 10% BENTONITE POWDER TO CREATE A SEAL THAT WILL PREVENT WATER FROM FOLLOWING THE NEW CONDUIT.
- ☐ BORE PIT COMPACTION SHALL BE A MINIMUM OF 95% STANDARD PROCTOR DENSITY.

EASEMENTS

ADD THE FOLLOWING NOTES TO THE PLAT MAP


- ☐ NO TREES OR SHRUBS IN WEST FIELD IRRIGATION COMPANY EASEMENTS.
- ☐ NO TELEPHONE BOXES OR POWER BOXES IN WEST FIELD IRRIGATION COMPANY EASEMENTS.
- ☐ FENCES DISTURBED DURING CONSTRUCTION ACTIVITIES MUST BE REPLACED AND RETURNED TO PRE-CONSTRUCTION CONDITION, OR BETTER.
- ☐ IRRIGATION BOXES MAY NOT BE FENCED IN YARDS. DIRECT ACCESS (NOT THROUGH FENCES) MUST BE PROVIDED TO WEST FIELD IRRIGATION COMPANY FROM CITY STREETS.

BORING


- ☐ BORE PITS MUST BE PLACED COMPLETELY OUTSIDE THE CANAL RIGHT-OF-WAY.
- ☐ FILL BORE PITS WITH A MIXTURE OF NATIVE MATERIAL AND 10% BENTONITE POWDER TO CREATE A SEAL THAT WILL PREVENT WATER FROM FOLLOWING THE NEW CONDUIT.
- ☐ BORE PIT COMPACTION SHALL BE A MINIMUM OF 95% STANDARD PROCTOR DENSITY.
- ☐ TRENCH PLUGS ARE TO BE PLACED AT EACH END OF THE CASING.
- ☐ TRENCH PLUGS ARE TO EXTEND THE WIDTH OF TRENCH, 12 INCHES ABOVE AND BELOW CASING PIPES, AND WITH A THICKNESS OF 24 INCHES.
- ☐ TRENCH PLUGS SHALL BE A 10% BENTONITE AND 90% CLAY MIXTURE. AT LEAST 40% OF THE BACKFILL MATERIAL MUST PASS A NO. 200 U.S. STANDARD SIEVE PRIOR TO ADDING BENTONITE POWDER. THE BACKFILL MATERIAL SHALL THEN BE AMENDED BY ADDING AND THOROUGHLY MIXING COMMERCIAL BENTONITE POWDER WITH THE BACKFILL MATERIAL AT A RATIO OF ONE-PART BENTONITE TO NINE PARTS BACKFILL MATERIAL. IMPERMEABLE FLOWABLE FILL IS AN ACCEPTABLE ALTERNATIVE.
- ☐ CONTRACTOR TO NOTIFY KYLE DEVANEY OF FRANSON CIVIL ENGINEERS WHEN TRENCH PLUGS ARE INSTALLED. VERIFICATION OF TRENCH PLUG COMPLETION MUST BE PERFORMED BY FRANSON CIVIL ENGINEERS BEFORE BACKFILLING. KYLE CAN BE REACHED AT 801-756-0309.
- ☐ IF REQUESTED, COMPACTION TEST RESULTS SHALL BE SUBMITTED TO FRANSON CIVIL ENGINEERS. ALL FAILED MATERIAL SHALL BE REMOVED AND COMPACTED TO SPECIFICATIONS. TESTING MUST BE PERFORMED BY A LICENSED SOILS LAB.
- ☐ WATER LINE PIPE INSIDE THE CASING SHALL HAVE RESTRAINING JOINTS.
- ☐ THRUST BLOCKS ARE REQUIRED ON ALL BENDS FOR DIP, PVC, OR PIP WATER LINES.

WEST FIELD
IRRIGATION COMPANY


	WEST FIELD IRRIGATION COMPANY													
	TYPICAL DRAWINGS													
	WFC NOTES													
	JOB NO.		02- General Notes.dwg 0-X2017 WFC West Field Irrigation Review/Standard Drawings											
	CU-0000108		LAYOUT: Cover											
SHEET														
2 OF 14														




A **INLET STRUCTURE PLAN**
NTS (FOR FLOWS >12 CFS)



1 **GRATE DETAIL**
NTS



2 **GRATE FRAME DETAIL**
NTS




4 **TRASHRACK DETAIL**
NTS


- NOTES:
1. IF BOX IS CAST IN PLACE, REBAR TO BE PLACED AT 12 INCHES ON CENTER (O.C.) EACH WAY (E.W.) MINIMUM.
 2. ALL PIPES INTO BOX SHALL BE GROUTED AND WATERTIGHT.
 3. SUBMIT TO CANAL COMPANY ENGINEER FOR APPROVAL.
 4. ENTIRE TRASHRACK TO BE HOT DIPPED GALVANIZED.
 5. MINIMUM TWO GRATES TO BE INSTALLED. SUBMIT TO CANAL COMPANY ENGINEER FOR APPROVAL.

TABLE 1 FOR DETAIL 5


TRASHRACK CONNECTIONS REQUIRED	
PIPE SIZE	NUMBER OF CONNECTIONS REQUIRED
24"	4
30"	5



B **INLET STRUCTURE PROFILE**
NTS




3 **GRATE CONNECTION DETAIL**
NTS




5 **TRASHRACK CONNECTION DETAIL**
NTS

DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.




1 DITCH PIPE CONNECTION
NTS (FOR FLOWS 12 CFS OR LESS)



2 TRASH RACK PLAN
NTS



A DITCH PIPE CONNECTION SECTION
NTS




C TRASH RACK SECTION
NTS

DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

NOTES:


1. IF BOX IS CAST IN PLACE, REBAR TO BE PLACED AT 12 INCHES O.C. E.W. MINIMUM.
2. ALL PIPES INTO BOX SHALL BE GROUTED AND WATERTIGHT.
3. SUBMIT TO CANAL COMPANY ENGINEER FOR APPROVAL OF FINAL DIMENSIONS ON REBAR REINFORCEMENT AND CONCRETE COMPONENTS.




B DITCH PIPE CONNECTION SECTION
NTS



D TRASH RACK FRONT SECTION
NTS



3 REBAR IN HEADWALL
NTS








4 REBAR IN FOOTING OF PIPE HEADWALL
NTS

WEST FIELD
IRRIGATION COMPANY

DESIGNER:	DRAFTSMAN:	CHECKED:	CHECKED:	PROJECT LEADER:	DATE
CHAD BROWN	MATT GURR			CHAD BROWN	MARCH 31, 2025
NO.	DATE	NTS	DESCRIPTION		

WEST FIELD IRRIGATION COMPANY
TYPICAL DRAWINGS
OPEN DITCH TO PIPE TRANSITION & STRUCTURE
04-Open Ditch to Pipe Transition.dwg
03/2017 WFIC West Field Irrigation Reviews/Standard Drawings
LAYOUT: Details



- ## NOTES:
1. LID DETAILS FOR BOX SHOWN ON SHEET  OR .
 2. BOX NOT TO BE PLACED IN DRIVEWAYS, ROADS, OR OTHER TRAFFIC AREAS.
 3. ALL PIPES INTO BOXES SHALL BE GROUTED AND WATERTIGHT.
 4. BOX WALL THICKNESS AND REINFORCEMENT ARE DEPENDENT ON SITE CONDITIONS AND DEPTH. MINIMUM SIZE AS SHOWN.
 5. DIMENSIONS SHOWN ON WALLS AND BOXES ARE MINIMUM SIZE. SPECIFIC SITE CONDITIONS OF BOXES AND WALLS MAY REQUIRE ADDITIONAL THICKNESS OR WIDTH.
 6. TRENCH PLUG TO BE PLACED IN LOCATION SHOWN FOR WIDTH OF TRENCH AND 12 INCHES ABOVE AND BELOW PIPE AT A THICKNESS OF 24 INCHES. PLUGS SHALL BE A 10% BENTONITE AND 90% CLAY MIXTURE.
 7. PLACE STRUCTURE ON 6-INCHES OF IRRIGATION COMPANY ENGINEER APPROVED COMPACTED BEDDING.

MINIMUM PIPE SLOPES		
PIPE SIZE	MIN. SLOPE, FT/FT	MIN. SLOPE, %
24"	0.0008	.08%
30"	0.00058	.058%

DISCLAIMER:

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

PARTS LIST		
No.	Name	Qty.
1	Frame	1
2	Cover	1
3	Wedge (Right & Left)	1 ea.
4	Stem	1
5	Wedge Bolts	4
6	Guide Rail	2
7	Stem Support	A/R
8	Head Rail	1
9	Lift Collar	1
10	Handwheel	1
11	Lift Nut	1
12	Limit Nut	1

A	B	C	D	E	F	G	H	J	K	L	M	N	P	Q	R	S	T	V	W
6	8	9%	4	7%	2½	10	24	3	3½	2%	7	3½	2¼	¼	-	-	-	6.160	6.645
8	10	12	4½	7%	2½	10	24	3	3¾	2½	9	3½	2¼	¼	4	7¼%	8	8.180	8.645
10	12	13½	6	7%	2½	10	24	3½	3¾	2½	11	3½	2¼	½	3½	9%	10	10.220	10.770
12	14	15%	7	7%	2½	10	24	4	3½	3	13	4	2¼	½	4	11%	12	12.270	12.780
14	16	17%	8	7%	2½	10	27	4¾	3¾	3¼	15	4	2¼	½	-	-	-	-	-
15	17	18%	8½	7%	2½	10	30	5	4½	3½	16	4	2½	½	4	14%	15	-	-
16	18½	20%	9%	7%	2½	10	32	5½	4½	3½	17	4½	2¼	¾	-	-	-	-	-
18	21	22%	10½	1	3½	12	34	6	4½	4¼	19	4½	2¼	¾	4	17¼%	18	-	-
20	23¼	25%	11¾	1	3½	12	38	7	4%	4	21	4½	2¼	¾	-	-	-	-	-
21	24	25%	12%	1	3½	12	40	7	4%	4	22	4½	2¼	¾	-	-	-	-	-
24	27¼	29%	13%	1	3½	12	44	8	5%	4%	25	4½	2¼	¾	-	-	-	-	-
30	33¾	36%	17%	1½	4	15	54	10	6	4½	31	6	2¼	¾	-	-	-	-	-
36	39¾	42%	20½	1½	4	15	62	12	6¼	5%	37	6	2¼	¾	-	-	-	-	-
42	45¾	48%	23%	1½	5	18	84	14	7	6	43	6	2½	¾	-	-	-	-	-
48	51%	54%	26%	1½	6	24	100	16	7%	6%	49%	6	2½	¾	-	-	-	-	-
54	58½	61%	30	2	6	30	100	18	7%	6%	55%	7	3	1	-	-	-	-	-
60	65	68	34	2	6	30	102	20	8%	7%	61%	8	3¼	1	-	-	-	-	-
72	77½	80¼	41	2	13	5	121	25½	10%	8%	73¼	8	3%	1	-	-	-	-	-

GATE DIMENSIONS IN INCHES


1 WATERMAN C-10 CANAL GATE
NTS

NOTES

1. TYPE 2 lubricated ball bearing lift used on 48" and larger gates.
2. Applies to spigotback gate only. Optional spigot, shown in separate detail.
3. All dimensions are also applicable for model CL-10 & CM-10 gates.
4. Add grout pad thickness to anchor bolt projection.
5. Type 3E 2:1 lift used, mounted to dual headrail.

Corrugated Pipe
Attached to Spigot
Back Frame

Type 4 Spigot




NOTE:
REBAR PER MANUFACTURER'S
SPECIFICATIONS.


A PLAN VIEW
NTS

DISCLAIMER:

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.




B SECTION
NTS




C SECTION
NTS

TABLE I
 $Q=3.367 LH^{3/2} @ L=3$

H (FT.)	Q (CFS)
0.2	0.90
0.3	1.66
0.4	2.56
0.5	3.57
0.6	4.69
0.66	5.42




I BAFFLE PLATE DETAIL
NTS




2 ANGLE IRON DETAIL
NTS

NOTES:

- IF BOX IS CAST IN PLACE REBAR TO BE PLACED AT 12" O.C. E.W. MINIMUM.
- DETAILS FOR CAST IN PLACE BOX SEE **2/5**.
- ALL PIPES INTO BOX SHALL BE GROUTED AND WATERTIGHT.
- SUBMIT TO IRRIGATION COMPANY ENGINEER FOR APPROVAL ON FINAL DIMENSIONS ON REBAR REINFORCEMENT AND CONCRETE COMPONENTS.
- PLACE STRUCTURE ON 6-INCHES OF IRRIGATION COMPANY ENGINEER APPROVED COMPACTED BEDDING.



A PLAN




C REBAR PLAN

DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

NOTES:

1. REINFORCING TO BE #4 REBAR @ 12-INCHES O.C. E.W. WITH 20-INCH MINIMUM SPLICE LENGTH.
2. REBAR TO BE BENT AT ANGLES OF STRUCTURES. OVERLAP TO BE IN STRAIGHT LENGTHS ONLY.
3. APPLICANT TO SUBMIT ACTUAL PLANS AND MATERIAL OF FLUME PRIOR TO CONSTRUCTION.




B PROFILE



D CROSS SECTION
NTS

TABLE I
HEAD-FLOW RELATIONSHIP
FOR CONCRETE FLUME


HEAD H _a (FEET)	FLOW Q (CFS)	HEAD H _a (FEET)	FLOW Q (CFS)
0.20	0.35	0.86	3.18
0.21	0.37	0.87	3.24
0.22	0.40	0.88	3.29
0.23	0.43	0.89	3.35
0.24	0.46	0.90	3.41
0.25	0.49	0.91	3.46
0.26	0.51	0.92	3.52
0.27	0.54	0.93	3.58
0.28	0.58	0.94	3.64
0.29	0.61	0.95	3.70
0.30	0.64	0.96	3.76
0.31	0.68	0.97	3.82
0.32	0.71	0.98	3.88
0.33	0.74	0.99	3.94
0.34	0.77	1.00	4.00
0.35	0.80	1.01	4.06
0.36	0.84	1.02	4.12
0.37	0.88	1.03	4.18
0.38	0.92	1.04	4.25
0.39	0.95	1.05	4.31
0.40	0.99	1.06	4.37
0.41	1.03	1.07	4.43
0.42	1.07	1.08	4.50
0.43	1.11	1.09	4.56
0.44	1.15	1.10	4.62
0.45	1.19	1.11	4.68
0.46	1.23	1.12	4.75
0.47	1.27	1.13	4.82
0.48	1.31	1.14	4.88
0.49	1.35	1.15	4.94
0.50	1.39	1.16	5.01
0.51	1.44	1.17	5.08
0.52	1.48	1.18	5.15
0.53	1.52	1.19	5.21
0.54	1.57	1.20	5.28
0.55	1.62	1.21	5.34
0.56	1.66	1.22	5.41
0.57	1.70	1.23	5.48
0.58	1.75	1.24	5.55
0.59	1.80	1.25	5.62
0.60	1.84	1.26	5.69
0.61	1.88	1.27	5.76
0.62	1.93	1.28	5.82
0.63	1.98	1.29	5.89
0.64	2.03	1.30	5.96
0.65	2.08	1.31	6.03
0.66	2.13	1.32	6.10
0.67	2.18	1.33	6.18
0.68	2.23	1.34	6.25
0.69	2.28	1.35	6.32
0.70	2.33	1.36	6.39
0.71	2.38	1.37	6.46
0.72	2.43	1.38	6.53
0.73	2.48	1.39	6.60
0.74	2.53	1.40	6.68
0.75	2.58	1.41	6.75
0.76	2.63	1.42	6.82
0.77	2.68	1.43	6.89
0.78	2.74	1.44	6.97
0.79	2.80	1.45	7.04
0.80	2.85	1.46	7.12
0.81	2.90	1.47	7.19
0.82	2.96	1.48	7.26
0.83	3.02	1.49	7.34
0.80	3.07	1.50	7.41
0.85	3.12		



A PLAN VIEW
NTS

DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.



B SECTION
NTS

FLOW TABLE
 $Q = CW \times H^{2.5}$


CW	2.5
H (FT.)	Q (CFS)
0.20	0.04
0.30	0.12
0.40	0.25
0.50	0.44
0.60	0.70
0.70	1.02
0.80	1.43
0.90	1.92
1.00	2.50
1.10	3.17
1.20	3.94
1.30	4.82
1.40	5.80
1.50	6.89




1 BAFFLE PLATE DETAIL
NTS

NOTES:

1. IF BOX IS CAST IN PLACE, PUT #4 REBAR PLACED AT 12" O.C. E.W. IN STRUCTURE FLOOR AND WALLS MINIMUM.
2. DETAILS FOR CAST IN PLACE BOX SEE **2/5**.
3. ALL PIPES INTO BOX SHALL BE GROUTED AND WATERTIGHT.
4. SUBMIT TO IRRIGATION COMPANY ENGINEER FOR FINAL DIMENSIONS ON REBAR REINFORCEMENT AND CONCRETE COMPONENTS.
5. PLACE STRUCTURE ON 6-INCHES OF IRRIGATION COMPANY ENGINEER APPROVED COMPACTED BEDDING



C SECTION
NTS




2 ANGLE IRON DETAIL
NTS

WEST FIELD
IRRIGATION COMPANY


NO.	DATE	DESCRIPTION	CHECKED:	REVIEWED:	PROJECT LEADER:	DATE
			CHAD BROWN	MATT GURR	CHAD BROWN	MARCH 31, 2025

WEST FIELD IRRIGATION COMPANY
TYPICAL DRAWINGS
90D V-NOTCH WEIR
08-90° V-Notch Weir.dwg
03/2017 WFC West Field Irrigation Reviews/Standard Drawings
LAYOUT: Details (11x17)
JOB NO.
CU 0000108



2 SOLID LID
NTS

3 BUBBLE UP BOX SECTION




DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

- NOTES:
- ALL PIPES INTO BOX SHALL BE GROUTED AND WATERTIGHT.
 - BOXES MAY BE PRECAST OR CAST IN PLACE. BOXES SHALL HAVE A MINIMUM INTERIOR WIDTH AND LENGTH OF 4 FEET WITH #4 REBAR @ 12 INCHES O.C. BOXES MUST BE SUBMITTED FOR REVIEW.
 - TURNOUT AND DIVERSION BOXES SHALL NOT BE PLACED IN ROADWAY.
 - ALL EXPOSED METAL SHALL BE GALVANIZED.


WEST FIELD IRRIGATION COMPANY				WEST FIELD IRRIGATION COMPANY			
TYPICAL DRAWINGS				TYPICAL DRAWINGS			
IRRIGATION TURNOUT, AND DIVERSION BOXES				IRRIGATION TURNOUT, AND DIVERSION BOXES			
10-Irrigation Turnout Diversion Box.dwg				10-Irrigation Turnout Diversion Box.dwg			
03/2017 WFIC West Field Irrigation Review/Standard Drawings				03/2017 WFIC West Field Irrigation Review/Standard Drawings			
LAYOUT: Details				LAYOUT: Details			
JOB NO.				JOB NO.			
CU 0000108				CU 0000108			
SHEET				SHEET			
10				10			
OF				OF			
14				14			



A DIRECTIONAL DRILL AND MICROTRENCH PLAN
NTS



B DIRECTIONAL DRILL OR MICROTRENCH ABOVE CANAL CROSS SECTION
NTS



B DIRECTIONAL DRILL UNDER CANAL CROSS SECTION
NTS


DISCLAIMER:

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

NOTES:

1. BORE PIT COMPACTION TO BE 95% STANDARD PROCTOR DENSITY.
2. FILL BORE PITS WITH A MIXTURE OF NATIVE MATERIAL AND 10% BENTONITE POWDER TO CREATE A SEAL THAT WILL PREVENT WATER FROM FOLLOWING THE NEW CONDUIT.
3. CONDUIT MUST BE A MINIMUM OF 2 FEET BETWEEN THE TOP OF THE CONDUIT AND THE BOTTOM OF A BOX CULVERT OR CONCRETE-LINED CANAL, AND 4 FEET BETWEEN THE TOP OF THE CONDUIT AND THE EARTHEN CANAL BOTTOM.
4. BORE PITS MUST BE COMPLETELY PLACED OUTSIDE OF THE DITCH RIGHT-OF-WAY.

WEST FIELD IRRIGATION COMPANY										TYPICAL DRAWINGS										DIRECTIONAL DRILLING AND MICROTRENCHING										11- Directional Drilling.dwg 03/2017 WFIC West Field Irrigation Reviews/Standard Drawings										CU 0000108										SHEET 11 OF 14									
DESIGNER: CHAD BROWN										DRAFTSMAN: MATT GURR										CHECKED: CHAD BROWN										REVIEWED: CHAD BROWN										PROJECT LEADER: CHAD BROWN										PRINT DATE: MARCH 31, 2025									



NOTES:
I. MAXIMUM LIFT IS 12" BEFORE COMPACTION


C PIPE BEDDING TRENCH SECTION
NTS

DISCLAIMER:


THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

WEST FIELD
IRRIGATION COMPANY

DESIGNER:		DRAFTSMAN:		CHECKED:		REVIEWED:		PROJECT LEADER:	
CHAD BROWN		MATT GURR		CHAD BROWN		CHAD BROWN		CHAD BROWN	
NO.		DATE		INTS.		REVISIONS			
						DESCRIPTION			



A CANAL BORING PLAN
NOT TO SCALE



B CANAL BORING SECTION
NOT TO SCALE

NOTES:

- BORE PIT COMPACTION TO BE 95% STANDARD PROCTOR DENSITY.
- TRENCH PLUGS ARE TO BE PLACED IN LOCATIONS SHOWN ON BOTH SIDES FOR WIDTH OF TRENCH AND 12 INCHES ABOVE AND BELOW CASING PIPES AND A THICKNESS OF 24 INCHES. PLUGS SHALL BE A 10% BENTONITE AND 90% CLAY MIXTURE.
- CONTRACTOR SHOULD NOTE CANALS ARE SOMETIMES USED FOR STORM DRAIN AND WILL COLLECT STORM WATER DURING AND FOLLOWING RAIN, SNOW, OR OTHER EVENT RESULTING IN WATER BEING DISCHARGED IN THE STORM DRAIN SYSTEM.
- WATERLINE PIPE INSIDE OF CASING SHALL HAVE RESTRAINING JOINTS.
- THRUST BLOCKS ARE REQUIRED ON ALL BENDS FOR DIP, PVC, OR PIP WATERLINES.
- CASING MUST BE A MINIMUM OF 2 FEET BELOW THE BOTTOM OF THE EXISTING CANAL BOX CULVERT OR 4 FEET BELOW EARTHEN OR CANAL BOTTOM.
- BORE PITS MUST BE COMPLETELY PLACED OUTSIDE OF THE CANAL RIGHT-OF-WAY.


TABLE I
STEEL CASING DIAMETER

DIAMETER (INCHES)	WALL THICKNESS (INCHES)
12	0.188
14 - 16	0.312
18	0.312
20 - 22	0.375
24 - 26	0.438
28 - 32	0.500
34 - 36	0.562
38 - 42	0.562

DISCLAIMER:

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.

THE DRAWINGS PROVIDED IN THESE STANDARDS ARE ONLY INTENDED TO SHOW THE TYPE OF FACILITY(IES) THAT WILL BE ACCEPTABLE TO THE WFIC. THESE ARE NOT INTENDED TO BE USED DIRECTLY IN THE DESIGN OF FACILITIES AS EACH ENCROACHMENT/CROSSING HAS ITS OWN UNIQUE CIRCUMSTANCE, DIMENSIONS, DESIGN CRITERIA, ETC. IT IS THE RESPONSIBILITY OF THE APPLICANT'S DESIGN ENGINEER, WHO WILL STAMP THE DRAWING, TO ENSURE THAT EACH PROJECT IS DESIGNED PROPERLY.



The diagram illustrates a plan view of a canal cross-section. A central rectangular area represents the canal, labeled "CANAL" at the top. A dashed line within this area indicates the "FLOW" direction, with an arrow pointing downwards. A "CUTOFF WALL BOTH SIDES" is shown as a solid line with a diagonal break, extending from the left side into the canal. The width of the canal is marked as "10' MIN." on the right side. The depth of the canal is marked as "1' MIN." on both the left and right sides. The "TOP OF CANAL BANK" is indicated on the left and right sides. The "BOTTOM OF CANAL" is indicated at the bottom. Three circular markers, each labeled "B 14" and "C 14", are positioned around the canal: one on the left, one on the right, and one at the bottom center. The background is filled with a cross-hatched pattern.

NOTE: INSTALL CONCRETE LINER ON MAIN CANAL IF CHANNEL IS CONCRETE LINED.

[illegible]

TYPICAL DRAWINGS CONCRETE LINER

14-Concrete Liner.dwg
O:\2017 WFIC West Field Irrigation Reviews\Standard Drawings
LAYOUT: Details

SPANISH FORK SOUTH
IRRIGATION COMPANY